CORPORATE INFOTECH PRIVATE LIMITED

Phone No :-0120-24317777,0120-24371666
website:- www.cipl.org.in
Mail id :- purchase@cipl.org.in

NICSI Supplier
ISO 9001:2008
ISO 20000-1:2005
ISO 27001:2005
CIN: U72900DL2007PTC162708

PURCHASE ORDER

Vendor :-
Leading Network Systems P Ltd
New Gat No.947,Avalwadi Road
Opp.Snehalaya School, Warehouse No.2,
Avalwadi, Wagholi, Dist.- Pune - 412207
GST #   27AABCL0651J1ZM
Kindly Attn :- Mr. Amjad Ali

PO No. :-	#218/CIPL_NOIDA/18-19
PO Date :-	04-09-2018
TAG ID:-	CIPL/TENDER/SITC/18-19/0037

S.no		Goods descp.	Qty	Unit Price (INR)	Total (INR)
1	CY-3842-03	Cyber Rack 42U, 800/1000D with Front Single & Rear single Perforated Door with Unique lock at front & rear door & side panels, Side panels set of 2 and castors set of 4, Blank Panels 4U & 5U(2-2 No.s), 1U Cable manager with PVS loops (4 No.s), 1U monitored Fann Tray with 4 Fans,	39	45513.00	1775007.00
2	AP8853	Rack PDU 2G, Metered, ZeroU, 32A, 230V, (36)C13 & (6)C19	78	26951.00	2102178.00
3	WMLC-A409-1	FLEXIBOX 19", 9U/500MMD 1 SECN with front glass door cam lock, (1) PDU 6x5Aamp and 1.5meter feed cable and 3 pin plug, (1) shelf 255m, (1) Fan 203v 90 cfm, (1)cable manager 1U pvc loops, Hardware pkt of 10 (Assembled)	23	4208.00	96784.00
		Please follow ANX-1 *(Compliance & Some other points) While ordering Order on OEM			
				Total:-	3973969.00
				Taxes 18%	715314.42
				Grand Total	**4689283.42**

Terms & Conditions

**Payment Terms	**90 DAYS PDC from the date of invocie.**
**Taxes	**Inclusive as above.**
**Delivery Mode	**Door Delivery *(freight charges inclusive)**
**Bill To Details	**Corporate Infotech Private Limited, E-81, SECTOR - 6, Noida-201301**
**CIPL'S GST NO.	**CIPL UTTAR PRADESH_____GST # 09AADCC0540R1ZF**
**CIPL'S PAN No.	**AADCC0540R**
**CIPL'S SERVICE TAX NO	**AADCC0540RST001**
**CIPL'S TIN NO.	**CIPL-UTTAR PRADESH___TIN # 09665708122**
**Ship To Details	**Corporate Infotech Private Limited, E-81, SECTOR - 6, Noida-201301**
**Special Instruction	**CIPL's PO no. to be mentioned in the invoice.**

THIS IS A SYSTEM GENERATED PO HENCE SIGNATURE NOT REQUIRED

Corporate Infotech Private Limited , HO:-E-81, Sec -6, Noida , U.P.- 201301
REG. OFFICES @ NEW DELHI, UTTAR PRADESH,HARYANA,PUNJAB,RAJASTHAN, PATNA, RANCHI, KOLKATA,CHENNAI

CORPORATE INFOTECH PRIVATE LIMITED

Phone No :-0120-24317777,0120-24371666
website:- www.cipl.org.in
Mail id :- purchase@cipl.org.in

NICSI Supplier
ISO 9001:2008
ISO 20000-1:2005
ISO 27001:2005
CIN: U72900DL2007PTC162708

PURCHASE ORDER

Vendor :-

Leading Network Systems P Ltd

New Gat No.947,Avalwadi Road
Opp.Snehalaya School, Warehouse No.2,
Avalwadi, Wagholi, Dist.- Pune - 412207
GST #   27AABCL0651J1ZM
Kindly Attn :- Mr. Amjad Ali

PO No. :-	#218/CIPL_NOIDA/18-19
PO Date :-	04-09-2018
TAG ID:-	CIPL/TENDER/SITC/18-19/0037

ANX- 1- COMPLIANCE

S.no	Requirement
	1. Server Racks
(i)	Server Racks : Central and DR Site – 42U & 8U Remote Site – 42U & 8U
(ii)	19" 42U racks shall be used. All the racks should be mounted on the floor with castor wheels with brakes (set of 4 per rack).
(iii)	Floor Standing Server Rack - Heavy Duty Extruded Aluminum Frame for rigidity. Top cover with FHU provision. Top & Bottom cover with cable entry gland plates. Heavy Duty Top and Bottom frame of MS. Two pairs of 19" mounting angles with 'U' marking. Depth support channels - 3 pairs. With an overall weight carrying Capacity of 500Kgs.
(iv)	The racks should accommodate industry standard 19" rack mount equipment.
(v)	Front and Back doors should be perforated with at-least 63% or higher perforations.
(vi)	All racks should be OEM racks with Adjustable mounting depth, Multi-operator component compatibility, Numbered U positions, Powder coat paint finish and Protective grounding provisions.
(vii)	All racks should have mounting hardware 2 Packs, Blanking Panel (4U to 5U size)
(viii)	All racks must be lockable on all sides with unique key for each rack
(ix)	Racks should be compatible with floor-throw as well as top-throw.
(x)	Racks should have Rear Cable Management channels, Roof and base cable access
(xi)	Wire managers :Two vertical and four horizontal
(xii)	Door ** The racks must have steel (solid / grill / mesh) front / rear doors and side panels. ** Both the front and rear doors should be designed with quick release hinges allowing for quick and easy detachment without the use of tools.
(xiii)	Monitored - Thermostat based - The Fans should switch on based on the temperature within the rack. The temperature setting should be factory settable. This unit should also include - humidity & temperature sensor
(xiv)	Depth :Min. 1000 mm
(xv)	Metal : Aluminum extruded profile
(xvi)	Side panel : Detachable side panels (set of 2 per Rack)
(xvii)	Width : 19" equipment mounting, extra width is recommended for managing voluminous cables
(xviii)	Sever racks should have Intelligent Power Distribution Units (PDUs) for effective power management.

Following Points To be followed Strictly

** Colour of the racks should be LIGHT GREY.

** Earthing bar should be mounted on isolators to the rack

** Earthing bar should be provisioned with necessary nut and bolts to engage\fix 4-6 sq mm lugs to facilitate the earthing of networking equipment mounted on the rack.

** All the product should be manufactured in 2018.

** Warranty- 3 Year from date of Purchase

** Material should not be made in china at all.

** Billing /Shipping to be done only after our mail confirmation

THIS IS A SYSTEM GENERATED PO HENCE SIGNATURE NOT REQUIRED